# Asian Inspired Nightstand


### © 2018/19 Mitch Peacock

## Basic Plans

( Enhanced plans available on my Etsy store Tree2Gift )



Supplied free to readers of my associated instructables post All copying and distribution rights reserved



Shaping Legs

Squared leg blanks are first produced, onto which all joints are prepared before any shaping is begun.

Back legs are shaped in two dimensions only, and therefore require just one cut.

Rear legs are shaped in three dimensions, requiring two cuts, rotating the leg by  $90^\circ$  after the first one.

Band saw, rasp, file, and card scraper, are used in that order to most easily shape the legs and prepare them for finish

Attaching Shelf Box To Legs

Shelf Rails are glued to grooves in legs and then bored and countersunk to accept one 1¾" steel counter sink screw into each joint.


The Shelf Box slides onto the shelf rails, and is bored from inside to accept two 1" steel counter sink screws into each rail.




Copright 2018 Mitch Peacock

Plans - Legs & Shelf Rails

3/4"






#### **Asian Inspired Nightstand**

Copright 2018 Mitch Peacock

Plans - Upper Rails

Nb. ALL Tenons in the Project:

Tenons should be prepared AFTER their respective mortises have been chopped. Adjust tenon layouts if their respective mortises mortises go awry.




Front Rail Preperation:

The Front Rail can be prepared by using halving joints between four horizontal and two vertical battens (as indicated here), or by joining the four horizontal battens with four cubes, using dowels.

Front Rail to Front Legs Joints:

Dowel joints are shown here, but dominos would also work well. Mortise and tenons could be prepared, but the small mortises would be tricky to chop.





Side Rail Preparation:


Side Rails can be shaped by piercing a solid board, or by laminating three pieces and leaving the holes out.


Attatching the Top:

To attach the top with buttons, the stopped groove in the side rails should be prepared. Alternative fixings, such as figure '8' washers, will likely require other arrangements.









#### Top Construction:


Top is made up of individual boards, edge glued together.

'Wings':

The rising breadboard ends are optional, and could be replaced with flat breadboard ends, or left off entirely in which case the stub tenons on the top boards are not required.


For seasonal movement, pin the breadboard ends through the tenons, each board receiving two 1/8" hardwood dowels. Elongate the holes in the tenon, along the boards width to allow movement. Only glue the front tenons, and the surfacing ends of the dowels. Drill from underneath and avoid coming through the top surface, unless you wich them to be on disrover.

you wish them to be on display.



Copright 2018 Mitch Peacock

Plans - Top



1 1/2